



Neil Bird:
082 855 0035
neil@securi-wall.co.za

SECURI-WALL

SECURI-WALL launched earlier this year and is taking the industry by storm with its simplicity and speed.

Take a good look at the photo taken using a drone and you will see that there is minimal civil work and the rest is all precast. The SECURI-WALL column is reinforced with high tensile steel and the wall slabs are prestressed with wire and strand. The compressive strength of concrete used is 50MPa.

The precast elements are installed using a mobile crane. The column heights vary between 3 to 3.6m, with a 2.4m column due in the near future.

Visit our website for more exciting applications using our system:



SECURI-WALL.CO.ZA



In accordance with the POPI Act, if you do not wish to receive these emails, please inform us in writing.